

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-039-20882-00-00  
Spot: SWNWSWSW Sec/Twnshp/Rge: 9-3S-26W  
810 feet from S Section Line, 4976 feet from E Section Line  
Lease Name: SHIRLEY Well #: 2-9  
County: DECATUR Total Vertical Depth: 3750 feet

Operator License No.: 30606  
Op Name: MURFIN DRILLING CO., INC.  
Address: 250 N WATER STE 300  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3749		175 SX
SURF	8.625	274		175 SX

Well Type: EOR UIC Docket No: E26599.1 Date/Time to Plug: 05/28/2014 9:00 AM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: JOHN TURNER Company: MURFIN DRILLING CO., INC. Phone: (785) 462-6781

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/700 # hulls.  
DV Tool at 2118' w/475 sx  
Perforations: 3531' - 3533', 3614' - 3618', 3650' - 3654' and 3674' - 3678'  
Casing leak at 2215' - 2557'

Plugging Proposal Received By: DARREL DIPMAN Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 05/28/2014 12:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3490' and pumped 80 sx cement w/250 # hulls. Pulled tubing to 2471' and pumped 80 sx cement w/250 # hulls. Pulled tubing to 1204' and pumped 80 sx cement w/200 # hulls to circulate cement to surface. Pulled all tubing and topped off 4 1/2" casing w/20 sx cement. Hooked to 8 5/8" x 4 1/2" annulus and pumped 15 sx cement. Shut in pressure 200 psi.

GPS: 39.80090N -100.25349W

Perfs:

Top	Bot	Thru	Comments
3674	3678		
3650	3654		
3614	3618		
3531	3533		

KCC WICHITA

JUN 12 2014

RECEIVED

Remarks: SWIFT TICKET # 26619

Plugged through: TBG

District: 04

Signed

Pat Bedore  
(TECHNICIAN)  
6/12/14  
cc to WCC 6/12/14

CM

JUN 04 2014

Form CP-2/3