

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-015-19349-00-00  
Spot: NWNWSENE Sec/Twnshp/Rge: 10-25S-3E  
3655 feet from S Section Line, 1079 feet from E Section Line  
Lease Name: ULMER Well #: 3  
County: BUTLER Total Vertical Depth: 2735 feet

Operator License No.: 34569  
Op Name: SONOMA RESOURCES LLC  
Address: PO BOX 384  
EL DORADO, KS 67042

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2722		
COND	15	77		
PROD	5	2721		
PROD	5.5625	2722		35 SX
SURF	15.5	77		0 SX
SURF	10	1653		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/16/2013 9:00 AM  
Plug Co. License No.: \_\_\_\_\_ Plug Co. Name: \_\_\_\_\_  
Proposal Rcvd. from: DAN FLOWERS/ SONOMA Company: SONOMA RESOURCES Phone: \_\_\_\_\_

Proposed Plugging Method: AS PRE KCC RULES & REGS

Plugging Proposal Received By: \_\_\_\_\_ WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 07/16/2013 9:00 AM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RAN TUBING TO BOTTOM AND CLEANED OUT HOLE. PULLED TUBING AND DROPPED SAND. RAN TUBING TO BOTTOM AND PUMPED 60 SXS OF 60X40 POZ. (<4% GEL). PULLED TUBING AND TAGGED BOTTOM PLUG AT 2525'. DUG OUT HEAD TO EXPOSE 15" CASING, PERFORATED AT 250'. RAN TUBING TO 250' AND CIRCULATED CEMENT BETWEEN 5" AND 10". RAN 1" TUBING DOWN BACKSIDE TO 250' AND BROUGHT CEMENT TO SURFACE. TOTAL TOP PLUG = 160 SXS.

Perfs:

Top	Bot	Thru	Comments
2710	2730		


KCC WICHITA  
JUN 02 2014

Remarks: PLUGGED DUE TO COMPLIANCE. NO ACTIVE LEASE.

RECEIVED

Plugged through: TBG

District: 02

Signed:   
6/19/14 (TECHNICIAN)