

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-083-21901-00-00
Spot: SWNESWNW Sec/Twnshp/Rge: 6-24S-22W
1715 feet from N Section Line, 783 feet from W Section Line
Lease Name: WHITESIDE HALES Well #: 2-6
County: HODGEMAN Total Vertical Depth: 4752 feet

Operator License No.: 31021
Op Name: CASTELLI EXPLORATION, INC.
Address: 6908 W 112TH
OKLAHOMA CITY, OK 73162

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4525		WITH 2 SX CMT
CIBP		4595		
CIBP		4694		
PROD	5.5	4745	2796	WITH 175 SX CMT
SURF	8.625	306		WITH 225 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/19/2014 12:00 PM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE INC. Phone: (620) 672-9100

Proposed Plugging Method: CIBP 50' ABOVE PERFS WITH 2 SX CMT. PLUG AT 1640' WITH 10 SX GEL & 40 SX CMT. PLUG AT 600' WITH 50 SX CMT. PLUG AT 320' WITH 50 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/19/2014 5:30 PM KCC Agent: NATHAN WILLIS

Actual Plugging Report:

CIBP @ 4525' WITH 2 SX CMT. 1ST PLUG AT 1648' WITH 10 SX GEL & 40 SX CMT. 2ND PLUG AT 593' WITH 50 SX CMT. 3RD PLUG AT 340' WITH 50 SX CMT. 4TH PLUG AT 42' WITH 15 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4602	4612		
4575	4582		

KCC WICHITA
MAY 27 2014

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

RECEIVED

Plugged through: CSG

District: 01

RECEIVED
MAY 21 2014
KCC DODGE CITY

Signed

Nathan Willis
6/17/14
(TECHNICIAN)