

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-22476-00-00
Spot: N2NWSWSE Sec/Twnshp/Rge: 17-19S-11W
1270 feet from S Section Line, 2310 feet from E Section Line
Lease Name: BIRZER Well #: 3
County: BARTON Total Vertical Depth: 3372 feet

Operator License No.: 4656
Op Name: DAVIS PETROLEUM, INC.
Address: 7 SW 26 AVE
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3369		225 SX
SURF	8.625	250		185 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/17/2014 2:00 PM
Plug Co. License No.: 99981 Plug Co. Name: COPELAND ACID & CEMENT, INC.
Proposal Rcvd. from: MIKE KASSELMAN Company: L D DRILLING Phone: (620) 793-3051

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/17/2014 5:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1350', 585' and 225'. Ran tubing to 3250' and pumped 100 sx cement. Pulled tubing to 1350' and pumped 50 sx cement. Pulled tubing to 600'. Circulated cement to surface with 60 sx cement. Circulated cement to surface on surface pipe with 40 sx cement. Pulled tubing. Topped off with 10 sx cement.

GPS: 38.39453 -098.56242

Perfs:

Top	Bot	Thru	Comments
3096	3100		

Remarks: COPELAND ACID AND CEMENTING

Plugged through: ESG

KCC WICHITA

MAY 21 2014

RECEIVED

District: 04

Signed

Bruce Rodie

(TECHNICIAN)

CM

MAY 15 2014