

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-191-22226-00-01
Spot: NWSWSESW Sec/Twnshp/Rge: 32-32S-1E
610 feet from S Section Line, 3832 feet from E Section Line
Lease Name: BARNES Well #: 2
County: SUMNER Total Vertical Depth: 4100 feet

Operator License No.: 33556
Op Name: DRAKE EXPLORATION, LLC
Address: 6535 12TH RD
DOUGLASS, KS 67039

String	Size	Depth (ft)	Pulled (ft)	Comments
PKR		4032		PACKER TYPE AND SETTING DEPTH: HALLIBURTON R4 SET @ 4032
PROD	8.875	1200		
PROD	4.5	4099		
SURF	5	250		
SURF	8.625	280		
T1	2.375	4032		

Well Type: EOR UIC Docket No: E30312.1 Date/Time to Plug: 03/11/2014 8:00 AM
Plug Co. License No.: 33556 Plug Co. Name: DRAKE EXPLORATION, LLC
Proposal Rcvd. from: DARREN BROYLES Company: DRAKE EXPLORATION Phone:

Proposed Plugging Method: SAND BACK 50' ABOVE PERFS & CAP WITH 4 SKS CEMENT. PERF AT 300' & CIRC CEMENT TO SURFACE.

Plugging Proposal Received By: STEVE VANGIESON WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/11/2014 10:30 AM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

KNOCKED OUT BRIDGE, SET CIBP AT 3400' WITH 2 SKS CEMENT. PERF 828'
PUMPED 75 SXS CEMENT. TAGGED CEMENT @ 778'. SHOT 4 SHOT @ 300' & CIRC
CEMENT TO 0'.

Perfs:

Top	Bot	Thru	Comments
4078	4084	CSG	

KCC WICHITA
MAY 23 2014
RECEIVED

Remarks: ELITE CEMENT. 60/40 4% GEL, COMPLIANCE TA'D WELL

Plugged through: CSG

District: 02

Signed

(TECHNICIAN)