

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-04914-00-00  
Spot: NENWNE Sec/Twnshp/Rge: 13-15S-13W  
330 feet from N Section Line, 1650 feet from E Section Line  
Lease Name: PARKER UNIT Well #: 03  
County: RUSSELL Total Vertical Depth: 3270 feet

Operator License No.: 6484  
Op Name: ANDERSON ENERGY, INC.  
Address: 300 W DOUGLAS AVE, STE 410  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3260		200 SX
SURF	8.625	267		200 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/06/2014 10:30 AM  
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.  
Proposal Rcvd. from: PRESTON DRIELING Company: ANDERSON ENERGY, INC. Phone: (785) 639-2099

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/400 # hulls.

Plugging Proposal Received By: RAY DINKEL Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 05/06/2014 12:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perforated at 1400', 725' and 225'. Ran tubing to 3100' and pumped 100 sx cement w/100 # hulls. Pulled tubing to 2100' and pumped 100 sx cement. Pulled tubing to 1100' and pumped 120 sx cement. Cement circulated out back side. POOH. Hooked to casing and pumped 50 sx cement. Cement circulated out braden head. Shut in and pressured up casing with cement.

GPS: 38.75383 -098.71338

Perfs:

Top	Bot	Thru	Comments
3218	3224		
2122	2148		

Remarks: ALLIED CEMENTING TICKET # 626923

Plugged through: TBG

KCC WICHITA

MAY 15 2014

RECEIVED

District: 04

Signed

Ray A. Dinkel

5/22/14

(TECHNICIAN)

CM

MAY 08 2014