

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-24399-00-00
Spot: E2SESESW Sec/Twnshp/Rge: 18-31S-8E
324 feet from S Section Line, 10847 feet from E Section Line
Lease Name: COOPER-HIATT Well #: 18-1A
County: COWLEY Total Vertical Depth: 2496 feet

Operator License No.: 33711

Op Name: B-C STEEL, LLC

Address: 1432 NIGHTHAWK RD
YATES CENTER, KS 66783

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2496	1200	80 SX
SURF	8.625	60		3 SX
SURF	8.652	460		150 SX

Well Type: GAS

UIC Docket No:

Date/Time to Plug: 03/11/2014 8:00 AM

Plug Co. License No.: 34685

Plug Co. Name: RCCA WELL SERVICE, LLC

Proposal Rcvd. from: ROGER ALTUS

Company: RCCA WELL SERVICE

Phone: (316) 648-5431

Proposed
Plugging
Method:

AS PER KCC RULES & REGS / 2220' PLUG, 510' CIRC TO SURFACE

Plugging Proposal Received By: B. J. HOPE

Witness Type: PARTIAL

Date/Time Plugging Completed: 03/31/2014 5:00 PM

KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG @ 2280', RCCA MIXED & PUMPED 35 SXS CLASS A COMMON & DISPLACED IN CASING. WAITED 2 HOURS, TAGGED CEMENT @ 2060', CUT CASING @ 1200', LAYED DOWN 1200' (33 JOINTS 4 - 1/2" CASING. 3-13-2014, RIH W/TBG @ 503', RCCA ESTABLISHED CIRCULATION, MIXED & PUMPED 250 SXS CLASS A COMMON 1% GEL TO SURFACE. CEMENT CIRCULATED. 3-31-2014, TAGGED CEMENT @ 85', TOPPED WELL BACK TO SURFACE W/30 SXS CLASS A COMMON. P&A COMPLETE. NO TICKET #.

Perfs:

Top	Bot	Thru	Comments
2272	2278	CSG	

Remarks: COMPLIANCE

KCC WICHITA

MAY 15 2014

Plugged through: TBG

RECEIVED

District: 02

Signed

DUANE KRUEGER
5/22/14
(TECHNICIAN)