

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-24379-00-00
Spot: SESENWNW Sec/Twnshp/Rge: 19-31S-8E
3969 feet from S Section Line, 10824 feet from E Section Line
Lease Name: COOPER-HIATT Well #: 19-1
County: COWLEY Total Vertical Depth: 2384 feet

Operator License No.: 33711
Op Name: B-C STEEL, LLC
Address: 1432 NIGHTHAWK RD
YATES CENTER, KS 66783

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2384		110 SX
SURF	8.652	450		210 SX
T1	2.375	2384		

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 02/27/2014 8:00 AM
Plug Co. License No.: 34685 Plug Co. Name: RCCA WELL SERVICE, LLC
Proposal Rcvd. from: ROGER ALTUS Company: RCCA WELL SERVICE Phone: (316) 648-5431

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: B. J. HOPE WitnessType: PARTIAL
Date/Time Plugging Completed: 03/21/2014 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG @ 2380', RCCA MIXED & PUMPED 25 SXS CLASS A COMMON 1% CC & DISPLACED IN CASING. WAITED 2 HOURS, TAGGED CEMENT @ 2380'. 3-10-2014, RIH W/TBG @ 2322', RCCA MIXED & PUMPED 25 SXS CLASS A COMMON 1% CC & DISPLACED IN CASING. WAITD 2 HOURS, TAGGED CEMENT @ 2170'. RIH ON WIRELINE, CUT CASING @ 1170', LAYED DOWN 1170' (27 JOINTS 4 1/2" CASING. RIH W/TBG @ 503', RCCA ESTABLISHED CIRCULATION, MIXED & PUMPED 130 SXS CLASS A COMMON 1% GEL. CEMENT DID NOT CIRCULATE. TAGGED CEMENT @ 75', RCCA MIXED & PUMPED 28 SXS CLASS A COMMON TO SURFACE. CEMENT CIRCULATED. P&A COMPLETE. 3-21-2014. NO TICEKT #.

Perfs:

Top	Bot	Thru	Comments
2313	2317	CSG	

KCC WICHITA

MAY 15 2014

RECEIVED

Remarks: COMPLIANCE

Plugged through: TBG

District: 02

Signed DUANE KRUEGER
3/24/14 (TECHNICIAN)

1/2