

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-24392-00-00
Spot: SWSWNENW Sec/Twnshp/Rge: 19-31S-8E
4243 feet from S Section Line, 10091 feet from E Section Line
Lease Name: COOPER-HIATT Well #: 19-2
County: COWLEY Total Vertical Depth: 2834 feet

Operator License No.: 33711
Op Name: B-C STEEL, LLC
Address: 1432 NIGHTHAWK RD
YATES CENTER, KS 66783

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2428	1480	80 SX
SURF	8.625	450		135 SX
SURF	8.625	455		135 SX
TI	4.5	2428		

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 03/11/2014 8:00 AM
Plug Co. License No.: 34685 Plug Co. Name: RCCA WELL SERVICE, LLC
Proposal Rcvd. from: ROGER ALTUS Company: RCCA WELL SERVICES Phone: (316) 648-5431

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: B. J. HOPE Witness Type: PARTIAL
Date/Time Plugging Completed: 03/21/2014 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG @ 2428', RCCA MIXED & PUMPED 25 SXS CLASS A COMMON & DISPLACED IN CASING. WAITED 2 HOURS, TAGGED CEMENT @ 2213'. CUT CASING @ 1480', LAYED DOWN 1480' (37 JOINTS 4 1/2" CASING. 3-21-2014, RIH W/TBG @ 503', RCCA MIXED & PUMPED 8 SXS CLASS A COMMON 3% CC & DISPLACED IN CASING. WAITED 2 HOURS. RIH W/ TBG @ 503', RCCA ESTABLISHED CIRCULATION, MIXED & PUMPED 200 SXS CLASS A COMMON 1% GEL TO SURFACE. CEMENT CIRCUALTED. P&A COMPLETE. NO TICKET #.

Perfs:

Top	Bot	Thru	Comments
2300	2350	CSG	

Remarks: COMPLIANCE

Plugged through: TBG

KCC WICHITA

MAY 15 2014

RECEIVED

District: 02

Signed Duane Krueger
5/22/14 (TECHNICIAN)