

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-01646-00-00  
Spot: SWNW Sec/Twnshp/Rge: 35-9S-25W  
3300 feet from S Section Line, 4620 feet from E Section Line  
Lease Name: SPIES LEASE Well #: 1  
County: GRAHAM Total Vertical Depth: 4018 feet

Operator License No.: 34318  
Op Name: BEREXCO LLC  
Address: 2020 N. BRAMBLEWOOD  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
L1	3546	4		250 sx
PROD	5.5	4004		100 SX
SURF	8.625	118		100 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/06/2014 8:30 AM  
Plug Co. License No.: 34318 Plug Co. Name: BEREXCO LLC  
Proposal Rcvd. from: MARK LEIKER Company: BEREXCO LLC Phone: (316) 772-8649

Proposed Plugging Method: Squeezed at 2071' to 2102' w/100 sx cement, 1880' to 1980' w/150 sx cement.  
Ordered 275 sx 60/40 pozmix 4% gel cement w/300 # hulls.  
Shot perforations at 1340' and 200'.  
Bottom perforations at 3788' - 3792' and 3801' - 3986'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 05/06/2014 5:30 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Perfs:

Tied on to casing and pumped 145 sx cement w/300 # hulls. Topped off cement at 1500'. Ran 1 1/2" pipe to 1365' and pumped 80 sx cement. Tied on to back side and squeezed with 25 sx cement. Tied on to casing and squeezed with 15 sx cement. Hole standing full.

Remarks: GLOBAL CEMENT TICKET # 1317

Plugged through: DP

KCC WICHITA  
MAY 20 2014  
RECEIVED

District: 04

Signed: *Marvin Mills*  
5/22/14 (TECHNICIAN)

CM

MAY 13 2014