

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-033-21598-01-00
Spot: SWSESESE Sec/Twnshp/Rge: 7-32S-17W
150 feet from S Section Line, 350 feet from E Section Line
Lease Name: BROWN-TODD Well #: 1-7H
County: COMANCHE Total Vertical Depth: 5245 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: 3118 CUMMINGS RD PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5200		
COND	16	60		
	L1 4.5	9740	0	WITH 510 SX CMT
PROD	7	5604	2500	WITH 350 SX CMT
SURF	9.625	796		WITH 350 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 06/20/2014 11:00 AM
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.

Proposal Rcvd. from: _____ Company: _____ Phone: _____

Proposed Plugging Method: SET CIBP @ 5200' WITH 30 SX CMT. PLUG AT 1070' WITH 30 SX GEL & 50 SX CMT. PLUG AT 830' WITH 75 SX CMT. PLUG AT 300' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: NONE
Date/Time Plugging Completed: 06/20/2014 3:00 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SET CIBP @ 5200'. SPOT 35 SX COMMON CEMENT WITH 200# HULLS @ 5100'.
TAGGED TOC @ 5086'. SPOT ANOTHER 35 SX COMMON CMT WITH 200# HULLS @
5050'. TAGGED AT 4697'. 1ST PLUG AT 1070' WITH 30 SX GEL & 50 SX CMT. 2ND
PLUG AT 830' WITH 75 SX CMT. 3RD PLUG AT 300' WITH 50 SX CMT. 4TH PLUG AT
60' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5742	9740		
5086	5096		

Remarks: USED COMMON CEMENT BY SARGENT LILLARD. TMD=9704'

Plugged through: TBG

District: 01

RECEIVED

JUN 26 2014

KCC DODGE CITY

Signed

7/3/14

(TECHNICIAN)

KCC WICHITA

JUN 27 2014

RECEIVED