

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-25763-00-00
Spot: NENENWNE Sec/Twnshp/Rge: 24-18S-22W
200 feet from N Section Line, 1325 feet from E Section Line
Lease Name: B-F UNIT Well #: 1
County: NESS Total Vertical Depth: 4243 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: 3118 CUMMINGS RD PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4242	2090	WITH 175 SX CMT
SURF	8.625	222		WITH 150 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/20/2014 2:00 PM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: SCOTT CORSAIR Company: AMERICAN WARRIOE Phone: (785) 398-2270

Proposed Plugging Method: Sand off 50' of bottom and top off with 5 sacks of cement. Shoot off 5.5" casing at approximately 3000' and pull up to 1430' and place balanced plug of 50 sacks of cement. Pull casing to 700' and place balanced plug of 80 sacks of cement. Pull casing to 220' and place balanced plug of 50 sacks of cement. Pull casing out and top of 8.625" casing with cement. Cement: 60/40 poz, 4% gel.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: NONE
Date/Time Plugging Completed: 06/20/2014 5:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

SANDED OFF PERFS TO 4190' WITH 5 SX CMT. 1ST PLUG AT 1430' WITH 50 SX CMT. 2ND PLUG AT 700' WITH 120 SX CMT. 3RD PLUG AT 220' WITH 50 SX CMT. TOP OFF WITH 30 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4231	4241		

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: CSG

KCC WICHITA

JUL 01 2014

RECEIVED

District: 01

Signed Michael Maier
(TECHNICIAN)

7/3/14 CKM

RECEIVED
JUN 27 2014
KCC DODGE CITY

Form CH-2/3