

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-22812-00-00
Spot: SENESE Sec/Twnshp/Rge: 24-16S-26W
1648 feet from S Section Line, 317 feet from E Section Line
Lease Name: NICHEPOR Well #: 6
County: NESS Total Vertical Depth: 4570 feet

Operator License No.: 33984
Op Name: LUTZ, SCOTT T. TRUST
Address: 1645 W. SUNRISE MOUNTAIN RD PO
FAYETTEVILLE, AR 72702

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4569	0	WITH 200 SX CMT
SURF	8.625	302		WITH 200 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/20/2014 10:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: KENNY RUPP Company: SCOTT T. LUTZ TRUST Phone: (785) 798-5260

Proposed Plugging Method: RUN TBG TO BOTTOM & SPOT 50 SX CMT & 200# HULLS. PULL TBG TO 2000' & CIRCULATE CM TO SURFACE. PULL TBG & TOP OFF. TIE ONTO BACKSIDE & PUMP 50 SX CMT IF POSSIBLE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/20/2014 1:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

Perfs:

** 5/20/85: 250 SX CMT WAS PUMEPD DOWN THE BACKSIDE. RAN TEMPERATURE SURVEY & FOUND CMT AT 1300** COULDN'T GET ALL THE TBG OUT OF HOLE. WAS STUCK AT 3800'. TRIED FOR 2 DAYS TO GET FREE. RUN TBG TO 3800' & PUMP 50 SX CMT & 200# HULLS. PULLED TBG TO 2000' & PUMPED 275 SX CMT. CMT CIRCULATED TO SURFACE. PULLED TBG & TOPPED OFF WITH 25 SX CMT. TIED ONTO BACKSIDE & PRESSURED TO 500# IMMEDIATELY.

KCC WICHITA
JUL 01 2014
RECEIVED

Remarks: **COMPLIANCE ISSUE DENIED TA SI 10 YRS** USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES

Plugged through: TBG

District: 01

Signed Michael Maier
(TECHNICIAN)

7/3/14 CKM

RECEIVED
JUN 27 2014
KCC DODGE CITY

Form CP-2/3