

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-21750-00-00
Spot: SWSENW Sec/Twnshp/Rge: 17-13S-21W
2970 feet from S Section Line, 3630 feet from E Section Line
Lease Name: KELLER A Well #: 10
County: TREGO Total Vertical Depth: 4038 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4036		500 SX
SURF	8.625	259		170 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/24/2014 9:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: STAN FROETSCHNER Company: MURFIN DRILLING CO., INC. Phone: (785) 483-1197

Proposed
Plugging
Method:

Ordered 450 sx 60/40 pozmix 4% gel cement w/600 # hulls.

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/24/2014 1:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

2 3/8" tubing was shot off at 2900' before Murfin took over. Perforated at 250', 826', 1660' and 2300'. Ran tubing to 2770' and pumped 150 sx cement. Cement circulated. POOH. Hooked to casing and pumped 20 sx cement at 500 psi shut in. Hooked to braden head and pumped 5sx cement at 300 psi shut in.

GPS: 38.92267 -099.68226

Perfs:

Top	Bot	Thru	Comments
3932	3942		

KCC WICHITA
JUN 30 2014
RECEIVED

Remarks: QUALITY CEMENTING TICKET # 145

Plugged through: TBG

District: 04

Signed

Ray Dinkel

7/03/14

(TECHNICIAN)

CM

JUN 25 2014