

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-077-21745-01-01  
Spot: S2S2SWSE Sec/Twnshp/Rge: 16-35S-6W  
200 feet from S Section Line, 1980 feet from E Section Line  
Lease Name: GREEN Well #: 1-16  
County: HARPER Total Vertical Depth: 9448 feet

Operator License No.: 34192  
Op Name: SANDRIDGE EXPLORATION AND PRO  
Address: 123 ROBERT S. KERR AVE  
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
I1	7	5136		270 SX
L1	4.5	9164		475 SX
SURF	9.625	583		335 SX
T1	2.875	3915		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/08/2014 12:00 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: \_\_\_\_\_ Company: TITAN WELL SERVICE LLC Phone: (405) 828-4225

Proposed Plugging Method: PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK WitnessType: NONE  
Date/Time Plugging Completed: 01/08/2014 12:00 AM KCC Agent: KEN SCOFIELD

Actual Plugging Report:

OPERATOR PLUGGED AND ABANDONED THIS WELL DUE TO JUNK IN THE HOLE. RBP IN 7" @ 4203', TESTED TO 1000 PSI. TOP OF STUCK PACKER @ 3948'. CEMENT RETAINER SET @ 3900'. COMMON CEMENT PUMPED THROUGH PACKER INTO THE COTTAGE GROVE PERFS. 7" CSG CUT AND PULLED AT APPROX 3675'. HOLE FILLED WITH 9 LB/GAL MUD. 50 SXS PLUG @ 1125' TAGGED @ 1015'. 50 SXS PLUG @ 750' TAGGED @ 650'. CEMENT CIRCULATED TO SURFACE FROM 633'. 260 SXS.

Perfs:

Top	Bot	Thru	Comments
4055	4057	CSG	

Remarks:

Plugged through: TBG

District: 02

Signed

Ken Scofield  
7/3/14 CKM

(TECHNICIAN)

KCC WICHITA

JUN 26 2014

RECEIVED

Form CP-2/3

JK