

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-03755-00-01
Spot: NWNWSENW Sec/Twnshp/Rge: 3-17S-11W
3639 feet from S Section Line, 3635 feet from E Section Line
Lease Name: RADENBURG LEASE Well #: 4
County: BARTON Total Vertical Depth: 3350 feet

Operator License No.: 34318
Op Name: BEREXCO LLC
Address: 2020 N. BRAMBLEWOOD
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3346		100 SX
SURF	8.625	339		100 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/24/2014 1:00 PM
Plug Co. License No.: 34318 Plug Co. Name: BEREXCO LLC
Proposal Rcvd. from: CURT GABEL Company: BEREXCO LLC Phone: (785) 628-6101

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/24/2014 4:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perfs:

Perforated at 340'. Ran tubing to 3238' and pumped 120 sx cement w/100 # hulls. Pulled tubing to 1680' and pumped 70 sx cement w/100 # hulls. Pulled tubing to 729'. Circulated cement w/175 sx cement and 100 # hulls. Pulled tubing and topped casing off w/60 sx cement. Tied to surface pipe and pumped 20 sx cement. Pressured up and shut in.

GPS: 38.60540 -099.52934

Remarks: ALLIED CEMENTING

Plugged through: TBG

District: 04

Signed Bruce Rodie
7/8/14 CRM (TECHNICIAN)

CM