

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-055-00222-00-00
Spot: NW Sec/Twnshp/Rge: 1-22S-32W
3967 feet from S Section Line, 4016 feet from E Section Line
Lease Name: DAVIS Well #: 1-1
County: FINNEY Total Vertical Depth: 2760 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, INC.
Address: 6100 N WESTERN AVE PO BOX 18496
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2759	0	WITH 300 SX CMT
SURF	8.625	316		WITH 225 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 06/19/2014 3:00 PM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: DENNIS FRICK Company: CHESAPEAKE OPERATING Phone: (620) 277-0803

Proposed Plugging Method: PUMP 120 SX CMT & 250# HULLS TO 1500'. TEST CASING TO 700#. CMT BOND LOG 1350' TO TOC. PERFORATE & RUN TBG AS NECESSARY.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/19/2014 7:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 250# HULLS & 120 SX CMT VIA 5 1/2" CASING. DISPLACE WITH WATER TO 1600'. PRESSURE TEST CASING TO 700#. HOLDING. RUN CBL FROM 1350' TO 350'. TOC @ 550'. PERFORATE 4 HOLES AT 400'. RUN TBG TO 1345' & SPOT 80 SX CMT UP TO 550'. TOOH WITH TBG. PUMP 130 SX CMT VIA 5 1/2" CASING THROUGH PERFS & CIRCULATE CMT TO SURFACE LEAVING THE 5 1/2" CASING & 5 1/2" X 8 5/8" ANNULUS FULL OF CMT.

Perfs:

Top	Bot	Thru	Comments
2718	2728		

KCC WICHITA
JUL 03 2014
RECEIVED

Remarks: **COMPLIANCE ISSUE: DENIED TA LACK OF LEASE** USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: CSG

District: 01

Signed Ken Jehlik
7/8/14 CKM (TECHNICIAN)

RECEIVED
JUN 24 2014
KCC DODGE CITY