

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-21338-00-00
Spot: N2SESW Sec/Twnshp/Rge: 19-13S-16W
990 feet from S Section Line, 1980 feet from W Section Line
Lease Name: DREILING Well #: 5
County: ELLIS Total Vertical Depth: 3518 feet

Operator License No.: 34935
Op Name: DEXXON, INC.
Address: PO BOX 348
KIEFER, OK 74041

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3515		0 SX
SURF	8.625	220		125 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/26/2014 1:30 PM
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC
Proposal Rcvd. from: BRIAN OBERLE Company: DEXXON, INC. Phone: (620) 793-2299

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement
Squeezed at 470' - 500', 1113' - 1114' w/75 sx cement, 1133' w/450 sx cement.
PBTD- 3515'
Perforations: 3282' - 3415', 3512' - 3515', 3515' - 3518' ARB OH

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/26/2014 3:30 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Drilled out of casing at 840'. Put on notched collar and got back in to casing to 982'. Kept getting hung up. Pulled one joint of tubing. Rigged on to tubing with a swedge and mixed and pumped 115 sx cement to circulate cement up 4 1/2" casing. Pulled tubing. Rigged to 4 1/2" casing with a swedge and pumped 60 sx cement to circulate cement up 8 5/8" and 4 1/2" casing. Shut in 8 5/8" casing and pressured both 8 5/8" and 4 1/2" casing up with 200 psi and 200 psi shut in pressure.

GPS: 38.90325 -099.14371
990' FSL 3222' FEL
NW NE SE SW

Perfs:

Top	Bot	Thru	Comments
3515	3518		
3512	3515		
3282	3415		

Remarks: QUALITY OILWELL CEMENTING TICKET # 147

Plugged through: TBG

District: 04

Signed _____

7/8/14 CKM

(TECHNICIAN)

CM

JUN 27 2014