

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-049-22315-00-01
Spot: SESWNWSW Sec/Twnshp/Rge: 11-31S-12E
1349 feet from S Section Line, 4830 feet from E Section Line
Lease Name: VOTH Well #: 1 SWD
County: ELK Total Vertical Depth: 1665 feet

Operator License No.: 33343
Op Name: POSTROCK MIDCONTINENT PRODUC
Address: OKLAHOMA TOWER 210 PARK AVE.
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comment
PKR		501		PACKER TYPE AND SETTING DEPTH: BAKER SET @ 501'.
PROD	4.5	1665		165 SX
SURF	8.625	42		25 SX
T1	2.375	501		

Well Type: SWD UIC Docket No: D27935.0 Date/Time to Plug: 05/12/2014 12:00 AM
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC
Proposal Rcvd. from: KEN PAULIE Company: Phone: (620) 432-4200

Proposed Plugging Method: RUN TUBING TO TD, CEMENT THROUGH TUBING TO SURFACE, PULL TUBING OUT OF HOLE AND TOP WELL OFF W/ CEMENT.

Plugging Proposal Received By: DUANE SIMS WitnessType: NONE
Date/Time Plugging Completed: 05/13/2014 12:00 PM KCC Agent: DUANE SIMS

KCC WICHITA
JUL 03 2014
RECEIVED

Actual Plugging Report:

Ran 2" to 810' and hit solid. Contractor pumped 6 barrels of cement and cottonseed hulls, pulled up to 400' and pumped another 5 barrels of cement. Pulled 2" and topped well off. A total of 84 sacks of cement were used to plug this well.

Perfs:

RECEIVED
JUL 01 2014
KCC Chanute Dist. #3

DS

Remarks: WELL WAS PLUGGED BECAUSE OPERATOR DID NOT WANT TO MIT IT.

Plugged through: TBG

District: 03

Signed [Signature]
✓ cc: UIC (TECHNICIAN)
7/8/14 CKM