

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-19290-00-03
Spot: NENWNE Sec/Twnshp/Rge: 21-9S-18W
4950 feet from S Section Line, 1650 feet from E Section Line
Lease Name: PARADISE CREEK Well #: 207
County: ROOKS Total Vertical Depth: 3574 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3570		150 SX
SURF	8.625	223		175 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/24/2014 8:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: JOEL STULL Company: VESS OIL CORP. Phone: (785) 885-8240

Proposed Plugging Method: DV Tool at 1540' w/375 sx cement
Squeezed from 800' - 1500'
Production perforation: 3224' - 3574'

Ordered 500 sx 60/40 pozmix 4% gel cement w/600 # hulls.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/24/2014 11:50 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 3465'. Allied pumped 160 sx cement w/200 # hulls. Pulled tubing to 1512'. Allied pumped 150 sx cement w/200 # hulls. Circulated cement and PTOH. Topped off 5 1/2" casing w/20 sx cement. Casing is full. Pumped 10 sx down backside and pressured to 200 psi to shut in.

Perfs:

Top	Bot	Thru	Comments
3570	3574	OH	

Remarks: ALLIED CEMENT COMPANY TICKET # 55,365

Plugged through: TBG

District: 04

Signed

Richard Williams
7/8/14 CKM (TECHNICIAN)

CM

JUN 27 2014