

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-155-20600-00-00
Spot: NESWSWNW Sec/Twnshp/Rge: 6-22S-9W
3037 feet from S Section Line, 4916 feet from E Section Line
Lease Name: KEY Well #: 1
County: RENO Total Vertical Depth: 3720 feet

Operator License No.: 5141
Op Name: ZENITH DRILLING CORPORATION
Address: PO BOX 780428
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3620		200 SX
SURF	8.625	217		225 SX

Well Type: SWD UIC Docket No: E27558.1 Date/Time to Plug: 06/03/2014 12:00 PM

Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone:

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DAN FOX

WitnessType: PARTIAL

Date/Time Plugging Completed: 06/03/2014 4:00 PM

KCC Agent: B. J. HOPE

Actual Plugging Report:

SANDED BACK TO 3460' - CAPPED WITH 4 SXS CEMENT ON TOP. CUT CASING PIPE OFF @ 1710' PULLED CASING TO 1333' SPOTED 35 SXS CEMENT. TAGGED TOP CEMENT AT 1239'. PULLED CASING TO 770' SPOTED 35 SXS CEMENT. DID NOT TAG CEMENT. RAN ANOTHER 35 SXS CEMENT @ 770'. PULLED CASING OUT OF HOLE. RAN IN WITH TUBING TO 770' SPOTED 100 SXS CEMENT LET SET OVER WEEKEND. 6/2/14 TAGGED CEMENT @ 255'. RAN TUBING TO 216' CIRCULATED TO SURFACE WITH 85 SXS OF CEMENT.

Perfs:

Top	Bot	Thru	Comments
3554	3558		

KCC WICHITA
JUL 07 2014
RECEIVED

Remarks: COPELAND CEMENTING OUT OF GREAT BEND, USED COMMON WITH 3% CC, TICKET # FAILED MIT.

Plugged through: CSG

District: 02

Signed BJ Hope
✓cc: UIC (TECHNICIAN)
7/8/14 CKM

JK