

RECEIVED 11-13-81
 STATE CORPORATION COMMISSION
 NOV 13 1981
 CONSERVATION DIVISION
 Wichita, Kansas
 KCC# 6316

This form must be filed in triplicate with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within five days after the completion of the well, regardless of how the well was completed. Circle one: () gas, dry, SWD, OWWO, injection. Please type. Complete ALL sections. Applications must be filed for dual completion, commingling, salt water disposal and injection. Attach wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.) KCC# 6316 263-3238.

OPERATOR Holly Energy Corporations API NO. 15-033-20-467-0000

ADDRESS 2600 Diamond Shamrock Tower COUNTY Comanche

Lock Box 23, 717 N. Harwood St. FIELD Collier Flats

**CONTACT PERSON Dallas, TX. 75201 LEASE Baker Trust #1

Cathy Messbarger PRODUCING FORMATION Swope

PHONE 316-624-8141 WELL NO. 1

PURCHASER Kock Oil Company WELL LOCATION NE NW

ADDRESS Box 2256 660 Ft. from NORTH Line and

Wichita, Ks. 67201 1980 Ft. from WEST Line of

DRILLING CONTRACTOR Sage Drilling the SEC. 2 TWP. 34S RGE. 20W

ADDRESS 222 Sutton Place

Wichita, Ks. 67202

PLUGGING CONTRACTOR _____

ADDRESS _____


TOTAL DEPTH 5250' PBD 5173'

SPUD DATE 8-24-81 DATE COMPLETED 9-2-81

ELEV: GR 1788' DF 1796' KB 1799'

DRILLED WITH (CABLE) ROTARY (AIR) TOOLS

Report of all strings set — surface, intermediate, production, etc. (New)/(Used) casing.



Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
surface	12 1/2	8-5/8"	24#	661'	lite regular	300	1/2# flocele, 2% cc 3% cc
production	7-7/8	4 1/2"	10.5#	5249'	Class H	50	8% gel, 12 1/2# gil-sonite, 10% salt
					50/50 pozmix-	350	18% salt, 4% gel, 12 1/2# gilsonite, .75% CFR-2

LINER RECORD			PERFORATION RECORD		
Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2SPF	.38DP	4760-4770'

TUBING RECORD		
Size	Setting depth	Packer set at
2-3/8"	4736'	4736'

ACID, FRACTURE, SHOT, CEMENT		Depth interval treated
Amount and kind of material used		
2000 gal, 15% Spearhead Acid with Iron Control		4760-4770'

TEST DATE: 11-3-81 PRODUCTION

Date of first production 9-29-81 Producing method (flowing, pumping, gas lift, etc.) flowing A.P.I. Gravity 40

RATE OF PRODUCTION PER 24 HOURS Oil 80 Gas 200 Water -0- Gas-oil ratio 2500 CFPD

Disposition of gas (vented, used on lease or sold) venting Producing interval (ft.) 4760-4770' SWOPE

** The person who can be reached by phone regarding any questions concerning this information.

A witnessed initial test by the Commission is required if the well produces more than 25 BOPD or is located in a Basic Order Pool.

Name of lowest fresh water producing stratum OGALALLA Depth 200'
 Estimated height of cement behind pipe circulated

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time, tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Red Bed & Anhydrite	-0-	80'		
Red Bed	80'	2042'		
Anhydrite	2042'	2545'		
Dolomite	2545'	3287'		
Shale	3287'	4215'		
Lime & Shale	4215'	4440'		
Shale	4440'	4606'		
Shale & Lime	4606'	4759'		
Lime & Shale	4759'	4895'		
Shale	4895'	5157'		
Lime	5157'	5250'	TD	

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

A F F I D A V I T

STATE OF KANSAS, COUNTY OF SEWARD SS,


Keith Hill OF LAWFUL AGE, BEING FIRST DULY SWORN UPON HIS OATH, DEPOSES AND SAYS:

THAT HE IS Agent FOR Holly Energy Corporation OPERATOR OF THE Baker Truss LEASE, AND IS DULY AUTHORIZED TO MAKE THIS AFFIDAVIT FOR AND ON BEHALF OF SAID OPERATOR, THAT WELL NO. 1 ON SAID LEASE HAS BEEN COMPLETED AS OF THE 29 DAY OF September 19 81, AND THAT ALL INFORMATION ENTERED HEREIN WITH RESPECT TO SAID WELL IS TRUE AND CORRECT.

FURTHER AFFIANT SAITH NOT.

(S) Keith Hill
 Keith Hill, Agent

SUBSCRIBED AND SWORN TO BEFORE ME THIS 5 DAY OF November 19 81



Rhenda Van Meter
 NOTARY PUBLIC

MY COMMISSION EXPIRES: 8-14-85