



OK 2

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JAN 27 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Freeman of Garvey Drlg. Co. has this

date requested permission to plug the following described well:

Mr. Freeman guarantees payment of the plugging fee.

Operator's full Name: Cleary Petroleum Corp.

Complete Address: 310 Kernac Bldg. Oklahoma City, OK

Lease Name: Schumacher Well No. 1-17

Location: C SW Sec. 7 Twp. 34s Rge. 20 (E)(W)

County: Comanche Total Depth 5480 Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Freeman was instructed to plug the well as follows:

614 ft 8 5/8 surface pipe cemented with 400 sacks. Pump

35 sacks cement to 600 ft. Mud to 45 ft, plug, 1/2 sack

hulls, 15 sacks cement to surface. 2 sacks cement in rat

hole, 2 in mouse hole.

Pumped by Globe Cementing Co. Great Bend, Ks

Very truly yours,

M. Russell Babin
Conservation Division Agent