

State of Kansas

FORM - CP-2
Rev. 6-26-62

JOHN ANDERSON, Jr. Governor
RICHARD C. BYRD Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

AUG 20 1963

8-20-63
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Vaughn Francis of Terrel Drilling Co. has this date requested permission to plug the following described well:

Mr. Francis guarantees payment of the plugging fee.

Operator's full Name: Fred B. Anschutz

Complete Address: 1521 Wichita Plaza, Wichita, Kansas

Lease Name: Butts Well No. # 1

Location: C NW SE Sec. 6 Twp. 34 Rge. 20 (E) (W) W

County Comanche Total Depth 5400 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Francis was instructed to plug the well as follows:

292' of 8.5/8" surface pipe, cemented with 250 sacks.
Fill hole with mud to 260', 1st cementing plug, 1/2 sack hulls,
cement with 20 sacks. Fill hole with mud to 40', 2nd cement-
ing plug, 1/2 sack hulls, cement with 10 sacks to base cellar.
Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent