

State of Kansas



CP2

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
7-29-71
JUL 29 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Freeman of Garvey Drlg. Co. has this

date requested permission to plug the following described well:

Mr. Freeman guarantees payment of the plugging fee.

Operator's full Name: Zenith Drlg. Corp. & Blaik Oil Co.

Complete Address: Suite 600 200 W. Douglas Wichita, Ks

Lease Name: Lucas Well No. 1-34

Location: C SE/NW Sec 34 Twp. 34S Rge. 16 (E)(W) W

County: Comanche Total Depth 5258 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Freeman was instructed to plug the well as follows:

314 ft 8 5/8 surface pipe cemented with 300 sacks. Pump
35 sacks cement to 600 ft. 2nd plug at 300 ft with 25 sacks
cement. Mud to 40 ft, plug, 1 sack hulls, 10 sacks cement
to surface. 2 sacks cement in rat hole. 2 sacks cement
in mouse hole. Pumped by Halliburton Cementing Co.

Great Bend, Ks

Very truly yours,

A. Russell Bikerstone
Conservation Division Agent