

83

DISTRICT CONSERVATION AGENT'S REPORT

[Handwritten signature]

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 12-26

LOCATION NW-NW-SE

Cable Pool SEC. 4 TWP. 14 RGE. 15-W

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 4 Lease G.H. Witt

Operator Margaretta Billings Address Box #172 Russell-Kans.

Field _____ County Russell

Total Depth 3032 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 10 3/4 - 896 ft. Not cement.
6 1/4 casing set at 3032 ft. Both 10 3/4 & 6 1/4 had been
squeezed with cement means tens in the last
8 years - set Plug & 5 sacks of cement at 2840 ft.
Used hole with heavy mud. Shot off 6 1/4 & 10 3/4
casing at 300 ft. Set Rock Bridge & Pumped in
150 sacks of cement at 250 ft. Cement Plug from
250 to 200 ft. - mud to 200 ft. - Bridge & 100 sacks of
cement at the surface.

Barns & Sons - Plugging Contractors

RECEIVED

STATE CORPORATION COMMISSION

PLUGGING

FILE SEC 4 T 14 R 15 W

JUN 11 1952

6-11-52

BOOK PAGE 14 LINE 2

CONSERVATION DIVISION

Wichita, Kansas

C. H. Stouck
District Conservation Agent

Date 6-07-52