

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-033-20,550-6000

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name R. J. Patrick Operating Co.

Complete Address P.O. Box 1314 Liberal, Kansas 67901

Lease Name Dra Baber Well No. 4

Location 150' W of C-NE-NE Sec. 2 Twp. 34 Rge. 20 (East)(West)

County Comanche Total Depth 4830'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor N. R. G. Drilling Co. Inc.

Address Box 1157 Liberal Kansas 67901 License No. _____

Operation Completed: Hour: 3:15 PM Day: 21 Month: March Year: 19 82

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

1st plug 1180' with 60 bbl of cement. 2nd plug push rubber plug to 620' and pumped 35 bbl of cement on top of it. 3rd plug on solid bridge 40' to 0' with 10 bbl of cement. Then circulated 10 bbl of cement in rat hole & 5 bbl of cement in mouse hole. The cement was pumped through drill pipe with hole full of heavy mud. The plugging was accomplished by Halliburton Co.

Amount of Surface Casing: 642' of 8 5/8" Cement circulated

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Paul A. Luthie
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

STATE CORPORATION COMMISSION
RECEIVED
3-23-82
MAR 23 1982

Signed: _____
Conservation Division Agent
Wichita, Kansas

INVOICED

DATE 3-26-82

INV. NO. 9755-W