

KANSAS

FORM CP-3
Rev. 1-8-82

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number ⁰³³ 15-03-20524-0000 ✓200 Colorado Derby Building
Wichita, KS 67202Operator's Full Name Scandia Resources Inc. c/o Gould Oil Inc.Complete Address P.O. Box 8640 Wichita Kansas 67208Lease Name Beeley Well No. 1-28Location C-SW/4-NE/4 Sec. 28 Twp. 34 Rge. 16 (East) (West)County Comanche Total Depth 438'Abandoned Oil Well ☐ Gas Well ☐ Input Well ☐ SWD Well ☐ D&A ☒

Other well as hereinafter indicated _____

Plugging Contractor Eagle Drilling Co. Rig #1Address 210 Rockborough Bldg. 260 N. Rockwood Wichita Kansas 67206 License No. _____Operation Completed: Hour: 9:00 AM Day: 28 Month: February Year: 1982Plugging Operations attended by Agent?: All ☐ Part ☐ None ☒

The above well was plugged as follows:

They lost a bit in bottom of hole. 1st plug at 438' with 35 Sbk of cement. 2nd plug 40' to 0' on solid bridge with 10 Sbk of cement. Then circulated 10 Sbk of cement in rat hole & 5 Sbk cement in mouse hole. The cement was pumped through drill pipe with hole full of heavy mud. The plugging was accomplished by allied Cementing.

Amount of Surface Casing: 421' of 8 1/2" cement circulated

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Paul Luthi
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

They didn't call me back in time to get there to see plugging. But it will be did right.

INVOICED

DATE 3-10-82INV. NO. 9606-WSigned: Paul Luthi
Conservation Division Agent
STATE CORPORATION COMMISSIONMAR - 9 1982
3-9-82
CONSERVATION DIVISION
Wichita, Kansas