

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-033-20,548-0000

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Scandia Resources Co. Gould Oil Inc.

Complete Address Box 8640, 260 N. Rock Rd. Suite 210, Wichita Kansas 67208

Lease Name Bealey Well No. 1-28A

Location Q-SW/4-NE/4 Sec. 23 Twp. 34 Rge. 16 (East)(West)

County Comanche Total Depth 5297'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Eagle Drilling Inc.

Address 210 Rockborough Bldg. 260 N Rock Rd. Wichita, Kansas 67206 License No. _____

Operation Completed: Hour: 4:30 P.M. Day: 10 Month: March Year: 19 82

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

1st plug at 950' with 50 sbx of cement. 2nd plug pushed rubber plug to 380's pumped 35 sbx on top of it. 3rd plug 40' to 0' with 10 sbx of cement. Then circulated 10 sbx of cement in the rat hole. The cement was pumped through the drill pipe. The plugging was accomplished by allied cementing.

Amount of Surface Casing: 397' of 8 5/8" cement circulated with 200 sbx common cement with 29% gel + 3% C.C.

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Paul Luthi
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

RECEIVED
STATE CORPORATION COMMISSION

MAR 16 1982
3-16-82
CONSERVATION DIVISION
Wichita, Kansas

Signed: _____
Conservation Division Agent

INVOICED

DATE 3-17-82

INV. No. 9674-L