

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-033-20,566-0000

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name R. J. Patrick Operating

Complete Address Box 1314 Liberal, Kansas 67901

Lease Name Smith - Herbert Weede Well No. 1

Location C-SE-NW Sec. 6 Twp. 34 Rge. 19 (East)(West)

County Comanche Total Depth 5300'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor H. R. G. Drilling Inc.

Address Box 1157, Liberal, Kansas 67901 License No. _____

Operation Completed: Hour: 1:00 AM Day: 16 Month: July Year: 19 82

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

1st plug at 1280' with 40 sbp of cement. 2nd plug at 620' with 40 sbp of cement. 3rd plug on solid bridge at 40' to 0' with 10 sbp of cement. Then circulated 10 sbp of cement in each the rat hole + mouse holes. The cement used was common with 2% zell + 3% C.C. The cement was pumped through the drill pipe with the hole full of heavy mud. The plugging accomplished by Halliburton Co.

Amount of Surface Casing: 607' of 8 7/8" cement circulate

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Paul A. Luthie
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

RECEIVED
STATE CORPORATION COMMISSION

JUL 20 1982
7-20-82
CONSERVATION DIVISION
Wichita, Kansas

Signed: INVOICED
Conservation Division Agent
DATE 7-22-82
INV. NO. 725-W



15-833-70566-0000
BULK MATERIALS DELIVERY
AND
TICKET CONTINUATION

FOR INVOICE AND
TICKET NO. 112387

DATE 7-15-82	CUSTOMER ORDER NO.	WELL NO. AND FARM Sniff Weed #1	COUNTY Clark	STATE Kansas
CHARGE TO R J Patrick		OWNER R J Patrick	CONTRACTOR No. B112387	
MAILING ADDRESS		DELIVERED FROM Hugoton, Kansas	LOCATION CODE 50335	PREPARED BY Don Phillips
CITY & STATE		DELIVERED TO Loc. E/S Protection K.	TRUCK NO.	RECEIVED BY

PRICE REFERENCE	SECONDARY REF. OR PART NO.	CODE		DESCRIPTION	UNITS 1		UNITS 2		UNIT PRICE	AMOUNT		
		L	D		QTY.	MEAS.	QTY.	MEAS.				
504-043				Southwestern T H/F Bushland, Tx.	110				6.39	702	90	
507-277				Halliburton Added Gel (3)	110				.37	40	70	
509-406				Calcium Chloride B/W 110 Cnt.	3				21.00	63	00	
<p>RECEIVED STATE CORPORATION COMMISSION JUL 20 1982 7-20-82 CONSERVATION DIVISION Wichita, Kansas</p>												
			Returned Mileage Charge	TOTAL WEIGHT	LOADED MILES	TON MILES						
				SERVICE CHARGE ON MATERIALS RETURNED		CU. FEET						
500-207				SERVICE CHARGE		CU. FEET	116		.95	110	20	
500-306			Mileage Charge	10,785 TOTAL WEIGHT	70 LOADED MILES	TON MILES	377.475		.70	264	23	
No. B 112387							CARRY FORWARD TO INVOICE		SUB-TOTAL			11.11