


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Comanche County, Sec. 24 Twp. 34S Rge. 20W  
Location as "NE/CNW $\frac{1}{2}$ SW $\frac{1}{2}$ " or footage from lines C-SE NW

Lease Owner K.R.M. Petroleum Corporation  
Lease Name G. C. Lemon Well No. 12  
Office Address 817 17th St., Denver, CO 80202  
Character of Well (Completed as Oil, Gas or Dry Hole) Dry Hole



Locate well correctly on above  
Section Plat

Date Well completed January 19, 1980  
Application for plugging filed Verbal Application 19  
Application for plugging approved Verbal Approval 19  
Plugging commenced January 19, 1980  
Plugging completed January 19, 1980  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production 19\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well William T. Owen  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 5,385'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	780'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy rotary mud from 5,385 ft. (rotary total depth) to 720 ft. Set plug at 720 ft. and cemented with 50 sacks cement. Filled hole with heavy rotary mud from 720 ft. to 40 ft. Set solid plug at 40 ft. and cemented to cellar with 10 sacks cement, 5 sacks cement in rat hole.

Plugging operations accomplished utilizing Halliburton Oil Well cementing pump truck through 4 1/2 inch drill pipe.

RECEIVED  
JAN 25 1980  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Halliburton Services  
410 Union Center Bldg., Wichita, Kansas 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.  
Gary Younger, Agent of owner) ~~XXXXXXXXXXXXXXXXXXXX~~

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Gary Younger  
200 N. Main, Wichita, Kansas 67202  
(Address)

SUBSCRIBED AND SWORN TO before me this 24th day of January, 1980



Elsie Willison  
Notary Public.

My commission expires July 25, 1982

KANSAS DRILLERS LOG

COMPANY K.R.M. Petroleum Corporation

SEC. 24 T. 34S R. 20W

FARM G. C. Lemon NO. 12

LOC. C-SE NW

COUNTY Comanche

ROTARY TOTAL DEPTH 5,385'

COMM. January 8, 1980

COMP. January 19, 1980

CONTRACTOR H-30, INC. (Rig #77)

ISSUED January 24, 1980

CASING

10 3/4"

8 5/8" Set at 780' cemented w/600 sxs cement

ELEVATION 1,746' GR.

5 1/2"

4 1/2"

FIGURES INDICATE BOTTOM OF FORMATIONS

Red Bed	780'
Red Bed and Anhydrite	1,477'
Shale	2,163'
Anhydrite and Shale	2,387'
Lime and Shale	5,385'
Rotary Total Depth	5,385'

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports..

H-30, INC.

*Gary Younger*  
Gary Younger

State of Kansas

County of Sedgwick


SS:

RECEIVED  
STATE COOPERATION COMMISSION

JAN 25 1980

1-25-80  
CONSERVATION DIVISION  
Wichita, Kansas

Subscribed and Sworn to before me a Notary Public  
in and for said county and state this 24th day of



January, 1980.

*Elsie Willison*  
Elsie Willison - Notary public

My Commission Expires:

July 25, 1982