

To: 1 051658 S-28
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 033-20,497-0000
C NW SE, SEC. 2, T. 34 S, R. 20 W/R
1980 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 30972

Lease Name Selzer Well # 8-2

Operator: Bishop Operating Co., Inc.

County Comanche 156.55

Name &

Address P.O. Box 1807

Well Total Depth 4817 feet

Hutchinson, KS 67504

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 612

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635

Address P.O. Box 251, Great Bend, KS 67530

Company to plug at: Hour: 12:30 p.m. Day: 28 Month: 5 Year: 19 93

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pullers, Inc. (phone) 316-793-9711

were: 5 1/2" at 4814' w/200 sx cement, PBTd 4300', Perfs at 4738-44'

1st plug sand back to 4050' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release 8 5/8" wiper plug and pump 120 sx cement.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:30 p.m. Day: 28 Month: 5 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug sanded back to 4050' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 120 sx cement.

Maximum pressure 500 psi and shut in 300 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3458' of 5 1/2" casing. RECEIVED
(If additional description is necessary, use BACK of this form.) STATE CORPORATION COMMISSION

I (did ~~not~~) observe this plugging.

DATE 6-4-93

Signed Richard W. Lacey JUN 4 1993
(TECHNICIAN) CONSERVATION DIVISION
Wichita, Kansas

WELL NO. 37837