

To: 1 051659 5-28
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 033-20,474 - 0000
C SW SE, SEC. 2, T. 34 S, R. 20 W/E
660 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 30972
Operator: Bishop Operating Co. Inc.
Name & Address: P.O. Box 1807
Hutchinson, KS 67504

Lease Name Selzer Well # 7-2
County Comanche 156.39
Well Total Depth 4812 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 646

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635
Address P.O. Box 251, Great Bend, KS 67530

Company to plug at: Hour: 1:45 p.m. Day: 28 Month: 5 Year: 19 93
Plugging proposal received from Gary Burke
(company name) Great Bend Casing Pullers, Inc. (phone) 316-793-9711

were: 5 1/2" at 4724' w/200 sx cement, Perfs at 4754-60'
1st plug sand back to 4700' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release 8 5/8"
wiper plug and pump 120 sx cement.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 2:45 p.m. Day: 28 Month: 5 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug sanded back to 4700' and dumped 5 sx cement on top of sand
through bailer,
2nd plug pumped 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released
8 5/8" wiper plug and pumped 120 sx cement.
Maximum pressure 400 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3155.5' of 5 1/2" casing. (If additional description is necessary, use BACK of this form.)
RECEIVED STATE CORPORATION COMMISSION

INVOICED
observe this plugging.

DATE 6-7-93

INV. NO. 37836

Signed Richard W. Lawrence
(TECHNICIAN) JUN 4 1993
64-93
CONSERVATION DIVISION
Wichita, Kansas