

To: 1 051669 6-14
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
203 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 033-20,473-0000
C SE SW, SEC. 2, T. 34 S, R. 20 W/E
660 feet from S section line
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 30972
Operator: Bishop Operating Company Inc.
Name & Address: P.O. Box 1807
Hutchinson, KS 67504

Lease Name Selzer Well # 6-2
County Comanche
Well Total Depth 4850 157.62 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 609

Abandoned Oil Well Gas Well Input Well SMD Well D&A
Other well as hereinafter indicated

Plugging Contractor Clarke Corporation License Number 5105
Address P.O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 12:45 p.m. Day: 14 Month: 6 Year: 19 93

Plugging proposal received from Jeff Sletto
(company name) Clarke Corporation (phone) 316-886-5665

were: 5 1/2" at 4849' w/200 sx cement, Perfs at 4764-67'
1st plug sand back to 4700' and dump 5 sx cement on top of sand through bailer,
2nd plug pump down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release 8 5/8" wiper plug and pump 125 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 1:40 p.m. Day: 14 Month: 6 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug sanded back to 4700' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement,

Maximum pressure 550 psi and shut in 400 psi.

RECEIVED
STATE CORPORATION COMMISSION
JUN 18 1993
6-18-93
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3500' of 5 1/2" casing.
additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.
DATE 6-24-93
XXXXXXXX

Signed Richard M. Leary (TECHNICIAN)

DATE 37983