

To: 1051656 S-28  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-033-20,444-0000  
C SW NW, SEC. 2, T. 34 S, R. 20 W/E  
3300 feet from S section line  
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 30972

Lease Name Selzer Well # 3-2

Operator: Bishop Operating Co. Inc.

County Comanche 156.45

Name & Address P.O. Box 1807

Well Total Depth 4814 feet

Hutchinson, KS 67504

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 640

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635

Address P.O. Box 251, Great Bend, KS 67530

Company to plug at: Hour: 10 a.m. Day: 28 Month: 5 Year: 19 93

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pullers (phone) 316-793-9711

were: 5 1/2" at 4814' w/170 sx cement, Perfs at 4748-54'

1st plug sand back to 4700' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release 8 5/8" wiper plug and pump 120 sx cement.

Plugging Proposal Received by Steve Middleton  
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:15 a.m. Day: 28 Month: 5 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug sanded back to 4700' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 120 sx cement.

Maximum pressure 500 psi and shut in 300 psi.

RECEIVED

STATE CORPORATION COMMISSION

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3219' of 5 1/2" casing.

(If additional description is necessary, use BACK of this form)

JUN 4 1993

INVOICED

I (did / ~~did not~~) observe this plugging.

DATE 6-7-93

6-4-93  
CONSERVATION DIVISION  
Wichita, Kansas

Signed Richard W. Lacy  
(TECHNICIAN)

NO. 37838