

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-039-20028-00-00
Spot: NE Sec/Twnshp/Rge: 4-4S-28W
1320 feet from N Section Line, 1320 feet from E Section Line
Lease Name: VAVROCH Well #: 13-W
County: DECATUR Total Vertical Depth: 2400 feet

Operator License No.: 34434
Op Name: EDISON OPERATING COMPANY LLC
Address: 8100 E. 22ND ST. N., BLDG 1900
WICHITA, KS 67226

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|------|------------|-------------|----------|
| PROD | 7 | 2399 | | 500 SX |
| SURF | 10 | 249 | | 250 SX |

Well Type: WSW UIC Docket No: _____ Date/Time to Plug: 05/13/2014 12:00 AM
Plug Co. License No.: 33645 Plug Co. Name: H2 PLAINS, LLC
Proposal Rcvd. from: ROCH MILLER Company: EDISON OPERATING CO Phone: (620) 786-5161

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/700 # hulls

Plugging Proposal Received By: DARREL DIPMAN WitnessType: NONE
Date/Time Plugging Completed: 05/15/2014 12:00 AM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Perforations at 2134', 2152' - 2160', 2172' - 2180' and 2188' - 2196. Ran in hole w/2 3/8" tubing string to 2146'. Pumped 1st cement plug of 175 sx cement w/400 # hulls. Pulled tubing to 1093' and pumped 2nd plug of 180 sx cement w/300 # hulls to surface. POOH w/tubing string. Topped off casing w/25 sx cement. Connected to surface casing and pumped 20 sx cement. Cut casing off 4' below G.L. and capped.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 2188 | 2196 | | |
| 2172 | 2180 | | |
| 2152 | 2160 | | |
| 2134 | 2142 | | |

Remarks: QUALITY PLUS OILFIELD SERVICES

Plugged through: TBG

District: 04

Signed Darrel Dipman
7/11/14 CKM (TECHNICIAN) CM

RECEIVED
KANSAS CORPORATION COMMISSION

JUL 09 2014
CONSERVATION DIVISION
WICHITA, KS

JUN 03 2014