

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-03124-00-01
Spot: NWNWSESE Sec/Twnshp/Rge: 11-9S-17W
1021 feet from S Section Line, 1104 feet from E Section Line
Lease Name: WESTHUSIN Well #: 8
County: ROOKS Total Vertical Depth: 3328 feet

Operator License No.: 34318
Op Name: BEREXCO LLC
Address: 2020 N. BRAMBLEWOOD
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	7	3431		150 SX
SURF	10.75	303		165 SX

Well Type: EOR UIC Docket No: E10108.2 Date/Time to Plug: 06/30/2014 9:30 AM
Plug Co. License No.: 34318 Plug Co. Name: BEREXCO LLC
Proposal Rcvd. from: CURTIS GABEL Company: BEREXCO LLC Phone: (785) 623-0546

Proposed Plugging Method: Perforations at 3151' to 3321'
Ordered 800 sx 60/40 pozmix 4% gel cement w/600 # hulls.
Shot perforations at 350'
Junk in hole at 3300'. Stuck hard.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/30/2014 2:45 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3300' and pumped 200 sx cement w/300 # hulls. Pulled tubing to 2300' and pumped 220 sx cement w/400 # hulls. Pulled tubing to 1300' and pumped 275 sx cement. Good circulation of cement. Pulled tubing out and topped off w/70 sx cement full. Tied on to backside and pumped 5 sx cement. Shut in pressure 500 psi.

GPS: 39.28005 -099.18050

Perfs:

Top	Bot	Thru	Comments
3157	3321		

Remarks: ALLIED CEMENTING TICKET # 55296

Plugged through: TBG

District: 04

Signed

CC: UIC
7/15/14 CKM

(TECHNICIAN)

KCC WICHITA

Form CP-2/3

JUL 14 2014

RECEIVED

JUN 07 2014