

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-153-21006-00-00  
Spot: NESEWNNE Sec/Twnshp/Rge: 29-3S-34W  
4527 feet from S Section Line, 1458 feet from E Section Line  
Lease Name: MAYR Well #: 1  
County: RAWLINS Total Vertical Depth: 4460 feet

Operator License No.: 33263  
Op Name: BOWMAN, WILLIAM F. DBA THE BILL  
Address: 2640 W RD  
NATOMA, KS 67651

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4444		105 sx
SURF	8.625	260		225 sx

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/10/2014 10:00 AM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: BILL BOWMAN Company: BOWMAN OIL Phone: \_\_\_\_\_

Proposed Perfs @3450'-4352'  
Plugging DV @2806 w/345 sx - circ.  
Method: Company accidentally perforated above TOC. Had mud coming into hole so had to run tubing. All cement at request of company.

Plugging Proposal Received By: CASE MORRIS WitnessType: NONE  
Date/Time Plugging Completed: 07/10/2014 10:00 AM KCC Agent: CASE MORRIS

Actual Plugging Report:

Perfs:

Ran tubing to 3400' and pumped 150 sx 60/40 4% gel cement w/300# hulls.  
Pulled to 2200' and pumped 100 sx cement  
Pulled to 1100' and circulated w/110 sx cement  
POOH. Topped off w/40 sx cement  
400 psi SIP

Remarks: SWIFT TICKET #26650

Plugged through: TBG

District: 04

Signed CASE MORRIS

7-15-14 CKM

(TECHNICIAN)

JUL 10 2014

KCC WICHITA Form CP-2/3

JUL 14 2014

RECEIVED