

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-03622-00-00
Spot: NENENE Sec/Twnshp/Rge: 20-9S-16W
4950 feet from S Section Line, 330 feet from E Section Line
Lease Name: DORR UNIT Well #: 702
County: ROOKS Total Vertical Depth: 3377 feet

Operator License No.: 6569
Op Name: CARMEN SCHMITT, INC.
Address: PO BOX 47
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3377		95 SX
SURF	8.625	235		120 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/30/2014 10:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: CURTIS HITCHMANN Company: CARMEN SCHMITT, INC. Phone: (620) 793-2540

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/600 # hulls.
Production perforations: 3128' - 3368'

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/30/2014 2:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Perforated at 2000', 1236' and 840'. Ran tubing to 3300' and pumped 100 sx cement w/250 # hulls. Pulled tubing to 2000' and pumped 50 sx cement. Pulled tubing to 1236' and pumped 125 sx cement w/100 # hulls to circulate cement to surface. Pulled all tubing. Topped off 4 1/2" casing w/60 sx cement and 150 # hulls. Hooked to 8 5/8" x 4 1/2" annulus. Pumped 25 sx cement. Shut in pressure 100 psi.

GPS: 39.26276N -099.12309W

Perfs:

Top	Bot	Thru	Comments
3337	3344		
3315	3324		
3128	3133		

Remarks: COPELAND ACID AND CEMENT TICKET # 42707

Plugged through: TBG

District: 04

Signed

Pat Bedore

7-15-14 ccm

(TECHNICIAN)

CM

JUN 07 2014

KCC WICHITA

Form CP-2/3

JUL 14 2014

RECEIVED