

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-19207-00-00  
Spot: SWSESE Sec/Twnshp/Rge: 17-9S-16W  
330 feet from S Section Line, 990 feet from E Section Line  
Lease Name: DORR B Well #: 5  
County: ROOKS Total Vertical Depth: 3359 feet

Operator License No.: 6569  
Op Name: CARMEN SCHMITT, INC.  
Address: PO BOX 47  
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3339		175 SX
SURF	8.625	242		150 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/03/2014 8:30 AM  
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.  
Proposal Rcvd. from: CURTIS HITSCHMANN Company: CARMEN SCHMITT INC. Phone: (620) 793-2540

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/600 # hulls.  
Ran tubing in hole to 1543'. Pulled tubing. Ran back in hole with bit to 1030' and began balling up. Pulled tubing back out and ran back in hole to 1580'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 07/07/2014 10:00 AM KCC Agent: PAT BEDORE

Actual Plugging Report:

Perforated at 1600'. Tubing at 1580'. Pumped 50 sx cement. Pulled tubing to 1220'.  
Perforated at 1230'. Pulled tubing to 790'. Perforated at 800'. Ran tubing back in hole to 1220'  
and pumped 100 sx cement w/100 # hulls. Pulled tubing to 600' and pumped 50 sx cement  
w/100 # hulls. Pulled all tubing and let well set for an hour. Ran tubing back in hole to 570'  
and pumped 100 sx cement w/250 # hulls. Pulled all tubing. Operator will run tubing back in  
hole on Monday 07/07/2014 and tag TOC.  
07/07/2014-Ran tubing back in hole. Tagged TOC at 330'. Pumped 30 sx cement to circulate  
cement to surface. Pulled all tubing. Topped off 4 1/2" casing w/5 sx cement. Hooked to  
8 5/8" x 4 1/2" annulus. Pumped 20 sx cement. Shut in pressure 200 psi.  
GPS: 39.26456N -099.12540W

Perfs:

Top	Bot	Thru	Comments
3326	3334		
3308	3316		
3290	3294		
3260	3266		
3222	3228		
3210	3216		
3198	3204		
3180	3183		
3142	3145		
3118	3124		
2351	2360		

Remarks: COPELAND ACIC AND CEMENT TICKET # 42712 AND 42713

Plugged through: TBG

District: 04

Signed \_\_\_\_\_

*Pat Bedore*

7-15-14 CKM

(TECHNICIAN)

CM

JUN 07 2014

KCC WICHITA

Form CP-2/3

JUL 14 2014

RECEIVED