

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-15054-00-00  
Spot: NENWNW Sec/Twnshp/Rge: 29-16S-11W  
330 feet from N Section Line, 990 feet from W Section Line  
Lease Name: ESFELD Well #: 9  
County: BARTON Total Vertical Depth: 3070 feet

Operator License No.: 32098  
Op Name: CLASSIC WELL SERVICE, INC.  
Address: BOX 539  
CLAFLIN, KS 67525

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3070		75 SX
SURF	8.625	562		300 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/08/2014 8:30 AM  
Plug Co. License No.: 32098 Plug Co. Name: CLASSIC WELL SERVICE, INC.  
Proposal Rcvd. from: FRED BECK Company: CLASSIC WELL SERVICE, INC. Phone: (620) 587-3402

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/400 # hulls.

Plugging Proposal Received By: BRUCE RODIE Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 07/08/2014 10:00 AM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perfs:

Ran tubing to 2960' and pumped 7 sx gel followed by 60 sx cement w/100 # hulls. Pulled tubing to 1650' and pumped 90 sx cement w/200 # hulls. Pulled tubing to 750'. Circulated cement to surface on casing with 90 sx cement and 100 # hulls. Shut in casing. Circulated cement to surface on surface pipe w/100 sx cement. Pulled tubing. Topped off w/30 sx cement.

GPS: 38.63702 -098.56895

Remarks: COPELAND ACID AND CEMENTING

Plugged through: CSG

District: 04

Signed

Bruce Rodie

7-15-14 CKM

(TECHNICIAN)

CM

JUL 10 2014

KCC WICHITA

Form CP-2/3

JUL 14 2014

RECEIVED