

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-24778-00-03  
Spot: N2SESWNE Sec/Twnshp/Rge: 20-19S-14W  
3220 feet from S Section Line, 1650 feet from E Section Line  
Lease Name: ROGERS Well #: 1  
County: BARTON Total Vertical Depth: 3547 feet

Operator License No.: 7383  
Op Name: GRADY BOLDING CORPORATION  
Address: 114 NORTH MAIN P.O. BOX 486  
ELLINWOOD, KS 67526

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3542		150 SX
SURF	8.625	808		240 SX
TI	2.375	1844		

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/12/2014 12:00 AM  
Plug Co. License No.: 32098 Plug Co. Name: CLASSIC WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD GUNN Company: GRADY BOLDING CORP. Phone: (620) 564-2240

Proposed Plugging Method: Ordered 210 sx 60/40 pozmix 4% gel cement w/200 # hulls

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 05/12/2014 12:00 AM KCC Agent: RAY DINKEL

Actual Plugging Report:

Rigged up. Pulled rods in singles and layed down tubing. Shut down for the day.  
05/13/14- Ran tubing in open ended. Copeland Cement mixed 110 sx cement w/100 # hulls at 1850'. Mixed 50 sx cement w/100 # hulls at 900'. Circulated cement at 400' w/50 sx cement. Shut in.

Perfs:

Top	Bot	Thru	Comments
3222	3226		
1760	1765		
1740	1750		

Remarks: COPELAND CEMENTING

Plugged through: TBG

District: 04

Signed

Ray Dinkel  
7-15-14 CKM

(TECHNICIAN)

CM

KCC WICHITA

Form CP-2/3

JUN 3 0 2014

JUL 14 2014

RECEIVED