

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-20078-00-00
Spot: S2SWSENE Sec/Twnshp/Rge: 7-15S-12W
2790 feet from S Section Line, 990 feet from E Section Line
Lease Name: KAUFMAN Well #: 3
County: RUSSELL Total Vertical Depth: 3302 feet

Operator License No.: 3134
Op Name: MORRIS, TERRY E. DBA G L M COMPA
Address: PO BOX 193
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	7	3295		140 SX
SURF	10.75	414		225 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/07/2014 9:30 AM
Plug Co. License No.: 34071 Plug Co. Name: PATRIOT WELL SERVICE, INC.
Proposal Rcvd. from: DAN Company: GLM COMPANY Phone: (785) 483-1599

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/21 sx gel and 600 # hulls.
No CP-1 found.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/07/2014 2:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report: _____ Perfs: _____

Perforated at 800' and 1500'. Ran tubing to 3000' and pumped 21 sx gel followed by 75 sx cement w/300 # hulls. Pulled tubing to 1500' and pumped 150 sx cement w/300 # hulls. Pulled tubing to 800' and pumped 135 sx cement. Cement circulated out back side. POOH. Hooked to casing and pumped 20 sx cement. Shut in pressure 300 psi. Hooked to braden head and pressured up to 400 psi.
GPS: 38.76314 -098.69258

Remarks: QUALITY CEMENTING TICKET # 553
Plugged through: TBG

District: 04 Signed Ray Dinkel (TECHNICIAN) CM
7-15-14 ckm

JUN 08 2014

KCC WICHITA Form CP-2/3
JUL 14 2014
RECEIVED