

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-21316-00-00
Spot: E2SESWSW Sec/Twnshp/Rge: 21-10S-19W
307 feet from S Section Line, 4041 feet from E Section Line
Lease Name: DICK LARGENT Well #: 3-21
County: ROOKS Total Vertical Depth: 3852 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3804		275 SX
SURF	8.625	278		175 SX

Well Type: SWD UIC Docket No: D20344.0 Date/Time to Plug: 07/02/2014 12:30 PM

Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.

Proposal Rcvd. from: JOHN GERSTNER Company: MURFIN DRILLING CO., INC. Phone: (785) 421-2101

Proposed TOC bottom stage at 2767'
Plugging DV Tool at 2733' w/600 sx cement
Method: TOC Top stage at 985'
Open hole completion 3804' - 3852'
Tubing parted at 946'. Fished tubing to 1102' and started loosing hole.
Ordered 400 sx 60/40 pozmix 4% gel cement w/600 # hulls.

Plugging Proposal Received By: RICHARD WILLIAMS

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 07/02/2014 3:00 PM

KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 992'. Tagged hard. Pulled tubing to 968'. Swift Services pumped 85 sx cement w/no hulls. Cement circulated. Pulled tubing out. Swift pumped 20 sx cement down casing. Locked up at 900'. Hooked up to backside and squeezed 30 sx cement. Maximum pressure 350 psi. Shut in pressure 300 psi.

Perfs:

Top	Bot	Thru	Comments
3804	3852		

Remarks: SWIFT SERVICES TICKET # 26645

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

✓ CC: UIC

7-14-15 CKM

KCC WICHITA

CM

JUN 07 2014

JUL 14 2014

Form CP-2/3

RECEIVED