

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-23171-00-00  
Spot: N2N2NE Sec/Twnshp/Rge: 5-15S-12W  
330 feet from N Section Line, 1320 feet from E Section Line  
Lease Name: SCHARTZ A Well #: 11  
County: RUSSELL Total Vertical Depth: 3361 feet

Operator License No.: 30606  
Op Name: MURFIN DRILLING CO., INC.  
Address: 250 N WATER STE 300  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3357	1623	265 SX
SURF	8.625	714		300 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/08/2014 8:00 AM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: STAN FROETSCHNER Company: MURFIN DRILLING CO., INC. Phone: (785) 483-1197

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 07/08/2014 1:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Ran tubing to 3200' and pumped 100 sx cement. Tagged cement at 2200'. Cut casing at 1623'. Pulled casing to 1381' and pumped 125 sx cement w/300 # hulls. Pulled casing to 750' and pumped 50 sx cement w/100 # hulls. Pulled casing to 350'. Circulated cement to surface with 130 sx cement. Pulled casing. Hole stayed full.

Perfs:

Top	Bot	Thru	Comments
3238	3242		
3212	3216		
3130	3133		
3097	3100		
3080	3082		
3010	3014		
2996	2998		
2946	2952		
2340	2348		

Remarks: COPELAND ACID AND CEMENTING

Plugged through: CSG

District: 04

Signed Bruce Rodie  
7-15-14 CKM (TECHNICIAN)

CM

JUL 10 2014

KCC WICHITA Form CP-2/3

JUL 14 2014

RECEIVED