

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-147-19076-00-00
Spot: SWNE Sec/Twnshp/Rge: 23-2S-19W
3300 feet from S Section Line, 1980 feet from E Section Line
Lease Name: HEFFRON Well #: 4
County: PHILLIPS Total Vertical Depth: 1447 feet

Operator License No.: 32016
Op Name: WELLS, RODGER D. DBA PIONEER RES
Address: 80 WINDMILL DR.
PHILLIPSBURG, KS 67661

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	1446		250 SX

Well Type: WSW UIC Docket No: _____ Date/Time to Plug: 06/23/2014 10:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: RODGER WELLS Company: PIONEER RESOURCES Phone: (785) 543-5556

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Perforations at 900' - 910'.
Perforated 5 1/2" casing at 200'

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/23/2014 12:30 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Perfs:

Ran tubing to 1400' and pumped 130 sx cement w/200 # hulls to circulate cement to surface. Tubing stuck in hole. Pumped another 50 sx cement down tubing and still stuck in hole. Hooked to backside and pumped another 40 sx cement down backside. Used tubing tongs to back tubing off. Backed off at 900'. Pulled 900' of tubing out of hole and topped off with 20 sx cement. 20 joints of tubing stuck in hole at 900'.

GPS: 39.86511N -099.42451W

Remarks: ALLIED TICKET # 55364

Plugged through: TBG

District: 04

Signed

Pat Bedore

7-15-14

(TECHNICIAN)

CM

JUN 07 2014

KCC WICHITA Form CP-2/3

JUL 14 2014

RECEIVED