

STATE OF KANSAS
STATE CORPORATION COMMISSION
201 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-033-20,457-000

LEASE NAME Wesley Girk

WELL NUMBER #2

SPOT LOCATION C-NW-SE

SEC. 1 TWP. 34 RGE. 20 ~~XX~~ or (W)

COUNTY Comanche

Date Well Completed 1-31-82

Plugging Commenced 7-7-1988

Plugging Completed 7-11-1988

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR R.J. Patrick Operating

ADDRESS P.O. Box 1314, Liberal, Ks. 67901

PHONE # 316 624,8483 OPERATORS LICENSE NO. 6528

Character of Well SWD
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? yes If not, is well log attached? _____

Producing formation Swope Depth to top 4777' bottom 4780' T.D. 4828'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Conductor				20"	60'	0'
Surface				8 5/8"	668'	0'
Production				4 1/2"	4827'	3430'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Pump 2 sks. hulls and 20 sks. cement to 4100' - pressured to 800 lbs. - Mud to 880'

Pump 40 sks. cement 880' to 760' - Mud to 880'

Pump 40 sks. cement 680' to 560' - Mud 560' to 40'

Put bridge and 10 sks. cement 40' to 3'

cut off 8 5/8", 3' below ground level and cap.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Midwest Casing Pulling Service License No. 6497

Address Box F, Sublette, Ks. 67877

STATE OF KANSAS COUNTY OF HASKELL, ss.

I, Edgar J. Eves (XXXXXXXXXXXX) or (operator) of above described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Edgar J. Eves
(Address) Box F, Sublette, Ks. 67877

RECEIVED
STATE CORPORATION COMMISSION
SEP 14 1988
7-14-88
CONSERVATION DIVISION
Wichita, Kansas

SUBSCRIBED AND SWORN TO before me this 11th day of July, 1988

Sondra L. Eves
Notary Public

My Commission expires: 12-16-88

