

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-033-20,429-0000

LEASE NAME Selzer

WELL NUMBER 2-2

4620 Ft. from S Section 1

4620 Ft. from E Section 1

SEC. 2 TWP. 34 RGE. 20 (S) or (W)

COUNTY Comanche

Date Well Completed -

Plugging Commenced 5-28-93

Plugging Completed 10:00 AM

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Bishop Operating Co., Inc.

ADDRESS P.O. Box 1807, Hutchinson, Kansas 67504

PHONE# (316) 662-6445 OPERATORS LICENSE NO. 30972

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 5-28-93 (d:

by Richard Lacey (KCC District Agent's Name

Is ACO-1 filled? Yes If not, is well log attached? -

Producing Formation Swope Depth to Top 4748 Bottom 4752 T.D. 4801

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	628	0
				5 1/2	4800	3509

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other were used, state the character of same and depth placed, from feet to feet each
Bottom Plug: Sanded to 4700 & bailed 5 sx cement.

Top Plug: Pumped 300 lb hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lb hulls, Wiper Plug, 125 sx cement, 60/40 with 6% gel. Had maximum pressure of 500 lbs, and 350 lbs shut in.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Great Bend Casing Pullers, Inc. License No. 4635 CP

Address Box 251, Great Bend, Kansas 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Bishop Operating Co., Inc.


STATE OF Kansas COUNTY OF Barton, ss.

Gary G. Burke

(Employee of Operator) I, Gary G. Burke, of the State of Kansas, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed, and the same are true and correct, so help me God.

(Signature) Gary G. Burke Pres

(Address) Box 251, Great Bend, Kansas



SUBSCRIBED AND SWORN TO before me this 1 day of June, 19 93

Anna K. Burke
Notary Public

My Commission Expires: 4-30-96

RECEIVED
STATE CORPORATION COMMISSION

JUN 2 1993
6-2-93
CONSERVATION DIVISION
Wichita, Kansas