

15-051 - 03239-0000

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Ellis SEC. 16 TWP. 15 RGE. 18 X/W
 Location as in quarters or footage from lines:
NE NE SE

Lease Owner Tomlinson Oil Co
 Lease Name Ohnmacht Well No. 4
 Office Address 200 W. Douglas, Wichita, Kansas 67202
 Character of Well (Completed as Oil, Gas or Dry Hole): oil
 Date Well Completed 12-28-62
 Application for plugging filed yes
 Plugging commenced 6-20-83
 Plugging completed 6-20-83
 Reason for abandonment of well or producing formation unprofitable

Locate Well
 correctly on above
 Section Platt.

Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Scheck
 Producing formation Arb Depth to top 3602 bottom 3610 T.D. 3610
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
Surface		0	233'	8 5/8"	233'	0
Prod Pipe		0	3610	5 1/2"	3603'	0
	DV Tool at 1213' with 300 sxs circ to surface					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Ran 2" tubing to 3600' spotted 15 sxs 50/50 Poz 6% gel 2% CCL with 2 sxs Cotton Seed Hulls, pulled tubing to 3450' mixed & spotted 11 sxs gel to 2440' set tubing at 2440' & spotted 40 sxs 50/50 Poz 6% gel, 2% CCL, filled casing to surface through tubing with same. Hooked on Braden Head & pressured 8 5/8" to 300# would not take any fluid.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sun Cementing Co

STATE OF Kansas COUNTY OF Ellis, ss.
Stanley Freeman (employee of owner) or (owner or operator) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Stanley Freeman
 Box 1588, Gt Bend, Kansas 67530
 (Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of June, 19 83

Shirley Wilkie
 Shirley Wilkie, Notary Public.

My Commission expires: January 29, 1984



RECEIVED
 STATE CORPORATION COMMISSION

JUN 28 1983

CONSERVATION DIVISION
 Wichita, Kansas