

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-033-20,474-0000

LEASE NAME Selzer

WELL NUMBER 7-2

660 Ft. from S Section 1

1980 Ft. from E Section 1

SEC. 2 TWP. 34 RGE. 20 (E) (W)

COUNTY Comanche

Date Well Completed NA

Plugging Commenced 5-28-93

Plugging Completed 4:00 PM

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Bishop Operating Co., Inc.

ADDRESS P.O. Box 1807, Hutchinson, Kansas 67504

PHONE# (316) 662-6445 OPERATORS LICENSE NO. 30972

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 5-28-93 (d)

by Richard Lacey (KCC District Agent's Name)

Is ACO-1 filed? yes If not, Is well log attached? \_\_\_\_\_

Producing Formation Swope Depth to Top 4754 Bottom 4760 T.D. 4812

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	646	0
				5 1/2	4724	3155

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each

Bottom Plug: Sanded to 4800 & bailed 5 sx cement.

Top Plug: Pumped 300 lbs hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lb hulls, wiper plug, 125 sx cement, 60/40 with 6% gel. Had maximum pressure of 400 lbs and 0 shut in.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Great Bend Casing Pullers, Inc. License No. -4635 CP

Address Box 251, Great Bend, Kansas 67530

RECEIVED  
STATE CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Bishop Operating Co., Inc.

STATE OF Kansas COUNTY OF Barton, ss.

Gary G. Burke


(Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the statements, and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.

(Signature) Gary G. Burke

(Address) Box 251, Great Bend, Kansas

SUBSCRIBED AND SWORN TO before me this 1 day of June, 1993



Anna K. Burke  
Notary Public

My Commission Expires: 4-30-96

Form  
Revised